

Sl. No.	Items of work	Unit	Rates estimated.	Quantity	Rates to be quoted
			Rs. a. p.		Rs.
4	Burnt brick in lime mortar	C.ft.	0 4 0	5,472	
5	Burnt stone slabs 5 to 6" thick one line dressed for exposed faces and fixed in lime mortar (old burnt stone slabs available at site)	S.ft.	0 2 0	928	
6	Providing trusses and fixing including painting, etc., as per Marin's specifications 10' from centre to centre	Cwt.	16 0 0	66	
7	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	389	
8	Roofing with 1st Class Mangalore pattern tiles on teak wood rafters 2" x 1"	Sqr.	22 0 0	59.84	
9	Teakwood doors frames 4" x 5" with panelled shutters 1½" thick folding doors with hinges, bolts, painting, etc., complete	S.ft.	1 12 0	68	
9a	Providing and fixing teak wood doors frames 3½" x 4" panelled shutters 1½" thick with hinges, bolts painting, etc., complete	"	1 8 0	77	
10	Teakwood windows with frames 3" x 4" with iron bars ¾" dia. 4½" c to c with glazed shutters hinges, etc., complete, expanded metal fixed inside, painting, etc., complete	"	2 0 0	288	
11	Chunam plastering	Sqr.	3 0 0	80.05	
11a	White washing 2 coats	"	0 4 0	80.05	
12	Flooring with burnt stone slabs over 3" lime mortar quoin dressing and fixed	Sqr.	20 0 0	39.00	
13	Mortar band over roofing	R.ft.	0 3 0	84	
14	Teakwood eave board from 12" to 9" wide ¾" thick including painting	"	0 8 0	360	
15	Mangalore ridge tiles set in mortar	"	0 7 0	136	
16	Cement pointing to basement	Sqr.	3 0 0	6.64	
17	Drilling holes in slabs for fixing girders	Each	0 4 0	54	
18	Providing and fixing R.C. ventilators	Sq.ft.	1 0 0	12	
19	Fixing R. S. Tatas tested girders above big doors including hoisting fixing and painting 6" x 3" at 12 lbs.	Cwt.	14 0 0	2.14	
20	Boxing girders with terrace brick in cement mortar	R.ft.	0 6 0	10	
21	Constructing steps in front of doors with available slabs	L.S.			20
22	Dismantling old mantapam design building now used as lumber Stores Shed as per details below:				
	(a) Removing parapet wall 1½ x 1½ of burnt brick in mortar including coping	R.ft.	0 0 4	290	
	(b) Removing burnt stone slab roofing with cement and stacking at places	Sqr.	3 0 0	26.04	
	(c) Removing beams 1' x 1' x 6'	Each	0 8 0	60	
	(d) Removing vertical pillars (11½' high) and stacking	"	0 8 0	40	
	(e) Removing capitals	"	0 4 0	40	
	(f) Removing size stone in mortar and removing debris	C.ft.	0 0 4	5,195	
	(g) Removing burnt stone slab flooring	Sqr.	3 0 0	2,301	
23	Old size stone in lime mortar	C.ft.	0 2 6	2,924	

B. R. GARUDACHAR,  
Executive Engineer.

#### MANDYA DIVISION.

Abstract Notification dated 16th December 1938.

The attention of the public is hereby invited to the Advertisement, published in pages 2267-2271 of the issue, dated 22nd December 1938 in *Mysore Gazette*, calling for tenders for constructing District Hospital at Mandya.

The last date of receipt of tender is up to 12 noon on 9th January 1939.

M. V. KRISHNASWAMY IYENGAR,  
Executive Engineer.